



project addresses the pressing issue of water scarcity threatening the deer population in Jaco Island, Nino Koni Santana National Park









Mitigate water scarcity through rainwater harvesting systems

Vision: Create a thriving ecosystem with sustainable water resources

Goal: Increase water availability for deer population



## Approach and Methods

- Prototype Development: Create a rainwater collection system with structure.
- Artificial Pond Construction: Direct rainwater to a strategically positioned pond.
- Pilot Testing: Assess system effectiveness by monitoring water levels and quality.



# Implementation Strategy

• Use sustainable materials like bamboo and industrial woods for structures.

 Repurpose fish plastic tanks for cost-effective rainwater collection.


















## Adult deer water consumption 2-4l/day

- Calculate the Volume of the Pond vol= L\*W\*Depth (2m\*2m\*0.5m) pond volume = 2 cubis meter
- 2. Annual rainfall 1500-2000mm in Jaco
- 3. Water collected: Volume= catchment area \* rainfall.


One pond could accumulate from 2 to 4 cubic meter of water equal to 2000l to 4000l of water.





Week 1 (March)	Planning and Preparation
Week 2 (March	Construction Begins
Week 3 (March	Construction Continues
Week 4 (April	Testing and Monitoring
Week 5 (April)	Refinement and Feedback
Week 6 (April)	Project Conclusion and Reporting





### Key Stakeholders:

- Village Leader: Represents the local community's interests and concerns. Provides insights into community needs and priorities.
- Youth Leader: Represents the younger generation within the community. Mobilizes youth volunteers and coordinates community engagement.
- Park Ranger: Manages and conserves the natural resources within the national park. Provides expertise on wildlife conservation and ecosystem management.





### PS: This budgeting done base on price survey

- Total Cost for Building and Implementing Pilot Project:
- Cost for Pond Construction (2 prototypes): \$170 x 2 =
   \$340
- Cost for Structure Construction (2 prototypes): \$285 x 2
  = \$570
- Adjusted Total Cost = 880

#### 2. Total Cost for Site Visit and Engagement:

Adjusted Cost: \$105

Considering the maximum budget limit of \$1,000 USD, the proposed budget plan falls within the allocated seed money.



